BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT11418

APPROVED SCHEDULE - B

Tender Notification No:EE/BTP/BBMP/E-PMT/19/2013-14, Date: 07.02.2014

Resurve fund to Emergency work in ward no. 06, Byatarayanprua sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N NARASIMHAIAH	
				In Figures	In Words
1	60	1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XXXXVII / I. 23) PWD SR 2013-14	Days	6619.2	Rupees Six Thousand Six Hundred Nineteen and Twenty Paise Only
2	180	1023 - Hire Charges of Tractor 40 HP including Operator and Fuel (P. XXXXVII / I. 19) PWD SR 2013-14	Days	1276.56	Rupees One Thousand Two Hundred Seventy Six and Fifty Six Paise Only
3	1800	Engaging Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2013-14 Page No. LV)	Nos	188.93	Rupees One Hundred Eighty Eight and Ninety Three Paise Only
4	325.73	KSRRB 300-2. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 152 / Item No. 19.2 / PWD SR 2013-14	cum	89.36	Rupees Eighty Nine and Thirty Six Paise Only
5	22.28	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No. 12 /Item No. 4.3 PWD SR - 2013-14	cum	4226.48	Rupees Four Thousand Two Hundred Twenty Six and Forty Eight Paise Only
6	35.1	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 PWD SR 2013-14 (P. 25 / I. 5.6)	Sqm	3496.71	Rupees Three Thousand Four Hundred Ninety Six and Seventy One Paise Only
7	58.5	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 122 / Item No. 15.3 / PWD SR 2013-14	Sqm	76.59	Rupees Seventy Six and Fifty Nine Paise Only
8	3.9	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. No. 12 / Item No. 4.6 / PWD SR 2013-14	cum	4707.32	Rupees Four Thousand Seven Hundred Seven and Thirty Two Paise Only

9	280.25	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.17 / Item No. 4.31 PWD SR - 2013-14	Sqm	267.01	Rupees Two Hundred Sixty Seven and One Paise Only
10	57.47	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 Page No. 13 / Item No. 4.11 PWD SR - 2013-14	cum	5555.16	Rupees Five Thousand Five Hundred Fifty Five and Sixteen Paise Only
11	43.1	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19 / Item No. 4.46.2 PWD SR 2013-14 TMT bar Fe 500	Qtl	7339.16	Rupees Seven Thousand Three Hundred Thirty Nine and Sixteen Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92